

Supporting Partner

5 - 8 DECEMBER 2022 DUBAI WORLD TRADE CENTRE

USING ADVANCED LAB TESTING TO ADDRESS SOME COMMON GEORISKS IN UAE

Dr MAN BUI AND ENG. EMAD SHARIF

DFI GEOTECHNICAL SUMMIT, THE BIG 5 GLOBAL 2022 5th December 2022, 16:30– 16:50 Sheikh Saeed Hall 2, Theatre 2 – Dubai World Trade Centre




ABOUT GTC LABORATORY IN DUBAI

ISO 17025:2017 Accredited by EIAC (Emirates International Accreditation Centre)







THERE ARE SOME COMMON GEORISKS IN UAE

SUCH AS:

- Collapsible of calcareous sand under shallow foundations
- Excessive permanent settlement after long term cyclic loads
- Large scale Surface settlement due to machine/ equipment vibration, especially for oil and gas facilities.
- Stability of deep excavation
- Uncertainties (various unknown) in site investigation due to technical limitations, site difficulties, site variations
- Actual soil behaviours, that hardly determined using in situ tests



Organized by







GEORISKS VS DAMAGED RISK COST

Optimal

damage risk cost

Risk Management, How to eliminate/ mitigate risk

Risk 2

Risk cost

Investment cost

Damage risk cost

Note: Using high factors of safety in foundation design may not eliminate the risks. The key is to address the right risks

Cost for building foundation can be reduced If we have a proper investment in soil investigation

Increasing risk mitigation

Organized by


Risk 1

€

dmg::events


Site Investigation Overview

ADVANCED LAB TESTING IS A CRUCIAL PART to ADDRESS THE GEORISKS



POPULAR WALL CRACKS IN PRIVATE VILLAS

Example of wall cracks of a private villa supported by shallow foundations on sand at al Warga, Dubai




Various serve cracks from front wall, back wall, sidewalls, first floor, second floors with various crack directions, led to high cost for remediation

What are the reasons? Can we prevent wall cracks?





THE SAND BENEATH THE FOUNDATION



- No GWT encountered in trial pits to 2.0m BGL
- Relatively higher water content at TP2 (5%-8%) increasing with depth.
- Water pipe line was previously broken and repaired, as clarified by the owner.
- ➔ Softened soil, reduction in soil shear strength and stiffness.

Ν

MEASUREMENT OF COLLAPSIBLE INDEX

MODERN 1D CONSOLIDATION SYSTEM WITH TAYLORED TESTING PROCEDURE


 Void ratio after remoulding 0 e0 Initial void ratio Axial strain Vertical strain [%] Soil collapsed Void ratio when saturated 3 Effective vertical stress [kPa] 1000

#THEBIG5EXHIBITION www.thebig5.ae

- **SLIGHTLY COLLAPSE INDEX (0.42%)**
- => Confirmation of the Different settlement e.g. of 12mm for a • layer of 3m (2 time the foundation width) thickness of calcareous sand



•






nts

Geotechnical & Engineering

Large scale oedometer tests

To remove the effect of particle size, and high pressure applied





```
Organized by
```



EXCESSIVE PERMANENT SETTLEMENT AFTER LONG TERM CYCLIC LOADS



www.thebig5.ae

ESPECIALLY FOR OIL AND GAS FACILITIES




Organized by



Different settlements beneath tank bottom annulus after 10-year operation exceeded acceptable limited as per API standard.



ASSESS THE FOUNDATION SETTELEMENT



www.thebig5.ae

OUR FEM CONFIRMED THIS \rightarrow THERE SHOULD BE SOMETHING ELSE?

nts

CREEP TEST IN TRIAXIAL CELL

BENEFIT OF LARGE SAMPLE SIZE & STRESS HISTORY SIMULATION



Stage	For g fi	ranular ll	For calcareous sand					
	s' _r (kPa)	s' (kPa)	s' _r (kPa)	s' (kPa)				
Overburden pressure	45	45	145	145				
Superstructure	45	75	145	175				
Hydrostatic test loading	45	265*	145	345 *				
Hydrostatic test unloading	45	75	145	175				
* Note: the summation of the hydrostatic test								


* Note: the summation of the hydrostatic test pressure, dead weight of the tank

Organized by



CREEP TEST IN TRIAXIAL CELL

Creep Test Results



Hydraulic-test load of 190 kPa > 170 kPa Oil pressure


- Creep monitored until almost deformation ceased.
- Creep could contribute up to 19 mm settlement for a 10 m layer of sand in the field << than the measurement settlement
- Meaning the Creep settlement may not be the major factor causing the excessive settlement of the tank.

Organized by



Simulation of the oil Tank operation in 10 Years

Using very Low frequency cyclic Triaxial tests in drained condition for both calcareous sand and granular fill



Some remarks from the laboratory simulation of oil tank

- The process of filling and emptying of the tank has caused the major settlement accumulated with time, observed for both dense calcareous sand and very dense granular engineering fill.
- It is likely that no further settlement taken place in the granular fill and in calcareous sand after 75 and 95 loading cycles, respectively, thanks to the stiffening effects in fully drained condition under cyclic load.
- Creep could partially contribute to the settlement but not represent the actual loading mode of the tanks, and Creep underestimated the long-term settlement of the tank.


• The creep rate of dense calcareous sand measured in the laboratory under effective stress of 190 kPa, was 0.19% per logarithmic time cycle, which exceeds the estimates made by empirical relations for 10 years period, whereas residual vertical strain resulted from cyclic loading and unloading is much higher.

Organized by




Ground/surface subsidence due to machine/engine vibration

ESPECIALLY FOR OIL AND GAS FACILITIES ON CALCAREOUS SAND e.g. ARTIFITIAL ISLAND




Higher lateral movement in Deep excavation than acceptable limit



Uncertainties In Measurement of c & ϕ for Sand & Soft Rock


Multiple stage triaxial test, set of three CID tests



dmg::events


Soil Drained vs undrained behavior

In triaxial tests, especially for Soil pamarmeters calibrated



Uncertainties in UCS Test Results will affect the design of Bored pile For Highrise Building


PILE BEARING CAPACITY AND SETTLEMENT



Reduce uncertainties in UCS Test

Testing procedure & specimen conformity assessment

sample	L/D	Bulk Density (g/cc)	Dry Density (g/cc)	Moisture content (%)	UCS (MPa)	e50	E50	
		(8/00)	(g/cc)	(/0)		(%)	(MPa)	
No #8	2.03	2.03	1.84	10.2	9.43	0.13	3682	
No #1	2.03	2.03	1.85	10.0	9.12	0.13	3626	
No #3	2.03	2.04	1.86	9.6	9.11	0.13	3439	
No #6	2.02	2.03	1.86	9.5	9.70	0.13	3690	
No #4	2.04	2.03	1.84	10.7	9.56	0.10	4935	





Organized by



REDUCE UNCERTAINTIES IN GEOPHYSICS SURVEYS

15

5

-15

15

5

r amplitude (V)

Trigger

amplitude (V)

Trigger


S

amplitude

Trigger

15

CONSISTENCY IN BENDER ELEMENT TEST



Concluding remark and suggestion

- For any project, a small and early investment in Advanced laboratory testing will yield a <u>much greater return value</u> for the project owner.
- All the key georisks shall be determined and addressed as early as possible from soil investigation stage .
- Advanced lab testing techniques as presented above shall be used to reduce BOTH the risk damaged cost and reduce the foundation building cost.


Organized by



Q & A

#THEBIG5EXHIBITION www.thebig5.ae Organized by













Talks













Project Management

Solar

Stone Design

Technology

Urban Design & Landscape